

Schedule of Quantity for: “Expansion of plate form for stocking the ore at Turamdih
Ground hopper.”

N. I. T No.: TMD/MIN – 721

[P R I C E P A R T]

Schedule of Quantity for: “Expansion of plate form for stocking the Ore at Turamdih Ground hopper

N. I. T No. TMD/MIN - 721

Item No.	Description of item	Qty	Unit	Rate Rs. P	Rate in words	Amount Rs. P
1	Earthwork in excavation in the following types of soil and rock upto and including 1.5 Metres lift including bailing/pumping out any water accumulating inside the excavated pit/trench, shoring, strutting(as directed by Engineer) adequate protection to be taken during excavation/drilling/blasting, transporting the excavated soil for all lead & stacking selectively including disposing off the rubbish, rock fragments, excess spoils etc. lead upto 100 Mtrs. in the area as directed by the Engineer, all complete as per drawing, specification and direction of Engineer.. a) Ordinary/dense soil mixed with gravels / rock fragments / lose waste.	1075.00	CUM			
	b) Ordinary rock	80.00	CUM			
2	Earth work in back filling with available earth including watering and compaction at all elevations around foundations, walls, wells, tunnels, pits, culverts, trenches, road approaches and in plinth filling & area filling as per specifications and drawings and as directed by the Engineer with selected spoil within a lead of 100 Mtrs.	650.00	Cum			

Item No.	Description of item	Qty	Unit	Rate Rs. P	Rate in words	Amount Rs. P
3	Clearing jungle including uprooting of rank vegetation, grass, brush, wood, trees and saplings of girth upto 30 cm measured at a height of 1m above ground level and removal of rubbish upto a distance of 50m outside the periphery of the area cleared.	2000.00	Cum			
4	Disposal/carriage of rubbish/waste rock/earth etc. dumped/stacked at site by mechanical means including loading, unloading and filling in layers not exceeding 20 cm. in depth, dressing properly and watering, rolling each layer and top most layer with power roller, (if required Vibratory roller to be used as directed by Engineer-in-charge), of minimum 8 to 10 tonnes capacity and dressing up the same, lead up to 2 K.M. and up to any lift including cost of all labour and equipment.	500.00	CUM			
5	Supply, mix place in position compact & cure cement concrete 1:3:6 (1 Cement: 3 coarse sand: 6) graded stone aggregate 20mm nominal size below foundations, walls, wells, pits, trenches etc. as per specifications, drawings and directions of the Engineer including cost of all materials, labour, tools and tackles etc. centering and shuttering, but excluding cost of cement.	30.00	CUM			

Item No.	Description of item	Qty	Unit	Rate Rs. P	Rate in words	Amount Rs. P
6	Supply, mix place in position compact & cure including testing of concrete specimens, finishing surfaces as per specifications, drawings and directions of the Engineer with nominal mix 1:1.5:3 (1 cement :1.5 coarse sand: 3 graded stone aggregate 20mm nominal size) including cost of all materials, labour, shuttering, but excluding the cost of cement and reinforcement. In foundation / plinth	612.00	CUM			
7	Providing dismantle and remove the form work of approved quality in walls with necessary scaffolding including required staging and supporting etc and necessary rendering of concrete surfaces after exposure at all elevations for all types of work with plywood shuttering including cost of all materials, labour, tools and tackles etc. complete as per specifications, drawings & directions of Engineer-in-charge. a) Foundation, footings, bases of columns etc for mass concrete	400.00	Sqm			
	b) Walls including attached plasters, buttresses, plinth and string courses etc.	1620.00	Sqm			

Item No.	Description of item	Qty	Unit	Rate Rs. P	Rate in words	Amount Rs. P
8	Supply, bend, bind and place the following types of reinforcement in all types of reinforced concrete work at all elevations, including cleaning, straightening, cutting, bending and binding with 18 SWG annealed wire or with welding such as tack, lap, butt etc. with approved electrodes, providing concrete cover blocks, pins, chairs, nails, supports of reinforcement etc. with all materials and labour complete as per drawings, specifications and directions of Engineer excluding cost of reinforcement High yield strength deformed bars.	41500.00	Kg			
9	Supplying and applying three(3) or more coats of approved water proof cement paint over a coat of primer to exterior surfaces of concrete, masonry, plastered surfaces etc. at all elevations and including preparation of surface, necessary scaffolding work etc. complete with all materials and labour (Application of paint should be made as per manufacturer's specifications.) to give an even shade.	800.00	Sqm			
	Total					
	Rebate if any in words (_____)				%	
	Grand Total					

Grand Total in words _____

Note:-

1. All items rates must be written in figures and words without which tenders are liable to be rejected.
2. All the pages of tender document must be duly signed by tenderer along with their seal.
3. Overall rebate, if any must be quoted in the above column only and written elsewhere shall not be considered.
4. Conditional tender submitted by the tenderer will be summarily rejected without any prejudice, hence tenderer are advice to quote their rates as per N. I. T conditions.
5. The quoted rate should be inclusive of all taxes and duties including Service Tax

Signature with seal