

URANIUM CORPORATION OF INDIA LIMITED
(Govt. of India Enterprise)
TURAMDIH MINES, EAST SINGHBHUM

UCIL/TMD/CIV-MIN/2022/1

April 20, 2022

To

- 1) M/s J. S. Furniture
- 2) M/s A. K. Enterprises, Jaduguda
- 3) M/s Prakash Kumar Singh, Sundernagar

Q U O T A T I O N

Sub: Renovation of SIT hall at Turamdih School

Dear Sir,

You are invited to offer sealed quotation for the subject work schedule of quantity in duplicate) in the enclosed schedule of quantity based on the terms and conditions given below: -

1. E. M. D your quotation must be accompanied with EMD Rs. **14, 220=00** in form of demand draft duly pledged in favour of Uranium Corporation of India Ltd. Payable at Jaduguda / Hartopa from any nationalized Bank of schedule Bank. Quotation without EMD shall summarily be rejected.
2. Income Tax /~~Sales Tax~~/work tax, if applicable shall be recovered at source on gross value of the work executed as per norms of the Corporation and balance amount on this account shall be deposited by the contractor directly to sales tax/income tax authority.
3. Completion time of work: Total work should be completed within **(30 days) Thirty days**, from the date of commencement of work, which shall be within 03 days from the date of issue of work order.
4. The offer must be valid for six months from the date of tender opening, and no contractor shall be allowed to withdraw his/their offer within this period
5. There will be defect liability period for this work shall be 12 (Twelve) months from the date of completion of this work.
6. The price quoted should be firm and no escalation on any account whatsoever will be entertained/paid by the Corporation.
7. Payment would be released by Jamshedpur/Jaduguda cheque.
8. First & final bill will be paid for this work.
9. The price quoted by tenderer should be firm and no escalation on any account what-so ever will be entertained /paid by the Corporation.

10. All the rates quoted by Tender shall be inclusive of cost of all materials, labour, tools, tackles, plant and machinery necessary to complete the work at no extra cost to corporation for any item.
11. No any carriage/transportation for any material except otherwise stated in schedule of quantities shall be paid by the department for this work. Contractor should quote their rates accordingly.
12. Quantity of an individual item may vary to any extent and be excluded altogether. Contractor will carryout all works up-to a total variation of $\pm 10\%$ (ten) on the contract price and all quoted rates shall remain firm within this limit.
- 13. Contractor must quote their rates against all the items in Schedule of quantities supplied along with this tender. If any contractor fails to quote any of the items, they have to execute without any payment.**
14. Scope of Work: Renovation of SIT hall at Turamdih School
15. Contractor has to follow guidelines of AERB (Atomic Energy Regulatory Board) issued time to time.
16. Quotations must be submitted in the enclosed schedule of quantity (original and two copies in Xerox of the same) duly signed along with seal of the agency. Duly filled quotations along with EMD shall be submitted in a sealed envelope and to be deposited in the office of Manager (Pers), Turamdih upto **26.04.2022** (12.00 Noon) and will be opened on same day at 3.30 P.M at Turamdih.
- 17. All other terms and conditions shall be applicable as per General conditions of UCIL's tender norms.**

Either in full or part thereof or to split up if necessary without assigning any reason whatsoever.

Thanking you,

Yours faithfully,
For Uranium Corporation of India Ltd.

(N. Patil)
D. G. M (Civil)

Encl: Schedule of quantity – 1 set

Copy to :-
1) Manager (Pers), TMD
2) Addl. Manager (A/C's.), TMD

Schedule of Quantity for: Renovation of SIT hall at Turamdih School

Quotation No: UCIL/TMD/CIV-MIN/2022/1, dated 20.04.2022

Item No.	Description of item	Qty	Unit	Rate Rs. P	Total in words	Amount Rs. P
1	Providing and fixing false ceiling at all heights with integral densified rod upto 1000 mm length and L-shape level adjuster of size 85x25x2 mm. Galvanised iron perimeter wall angle of size 22x19x0.40 mm of length 3000 mm to be fixed on periphery wall / partition with the help of plastic rawl plugs at 450 mm center to center and 40mm long dry wall S.S screws. The work shall be carried out as per specifications, drawing and as per directions of the Engineer-in-Charge. With 15 mm thick integral densified micro edge light weight calcium silicate false ceiling tiles sqm calcium silicate reinforced with fibre and natural filler false ceiling tiles of Size 595x595 mm of approved texture, design and patternshaving NRC (Noise Reduction coefficient) of 0.50 (minimum) as per IS 8225:1987, Light reflectance of 85% (minimum). Non combustible as per BS:476 (part-4), fire performance as per BS:476 (part 6 &7), humidity resistance of 100%, thermal conductivity < 0.043 W/m K as per ASTM 518:1991, in true horizontal level Including GST	90.00	CUM			
2	Designing, fabricating, testing, installing and fixing in position Curtain Wall with Aluminium Composite Panel Cladding, with open grooves for linear as well as curvilinear portions of the building , for all heights and all levels etc. including: Providing, fabricating and supplying and fixing panels of aluminium composite panel cladding in pan shape in metallic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral core sandwiched between two Aluminium sheets (each 0.5mm thick). The aluminium composite panel cladding sheet shall be coil coated, with Kynar 500 based PVDF / Lumiflon based fluoropolymer resin coating of approved colour and shade on face # 1 and polymer (Service) coating on face # 2 as specified using stainless steel screws, nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc (c) The fastening brackets of Aluminium alloy 6005 T5 / MS with Hot Dip Galvanised with serrations and serrated washers to arrest the wind load movement, fasteners, SS 316 Pins and anchor bolts of approved make in SS 316, Nylon separators to prevent bi-metallic contacts all complete required to perform as per specification and drawing The item includes cost of all material & labour component, the cost of all mock ups at site, cost of all samples of the individual components for testing in an approved laboratory, field tests on the assembled working curtain wall with aluminium composite panel cladding, cleaning and protection of the curtain wall with aluminium composite panel cladding till the handing over of the building for occupation. Base frame work for ACP cladding is payable under the relevant aluminium item.s The Contractor shall provide curtain wall with aluminium composite panel cladding, having all the performance characteristics all complete , as per the Architectural drawings, as per item description, as specified, as per the approved shop drawings and as directed by the Engineer-in-Charge. However, for the purpose of payment, only the actual area on the external face of the curtain wall with Aluminum Composite Panel Cladding (including width of groove) shall be measured in sqm. up to two decimal places. Including GST	125.00	Sqm			

	Total			
	Rebate if any in words (.....)		%	
	Grand Total			
		Total in words		

