

Schedule of quantities for : Acid resistant coating / lining in Day tank of ION exchange , leaching and unloading area at Turamdih Process plant

NIT No. TMD / 607 dtd 26-09-2014

Item No.	Description of Item	Unit	Quantity	Rate		Amount	
				Rs.	P.	Rs.	P.
1	2	3	4	5		6	
1	Providing and laying Acid Resistant Floor Coating (CES COTE CR 11 Flooring system 5mm thick; system comprising of 750 microns CES COTE CR 11 on top of epoxy 4mm screed mortar CES FLOR INTERMEDIATE 2000 laid over a coat of epoxy primer CES FLOR SLV Series Prime 90 with thickness of 250 microns) or equivalent system having minimum 5mm thick coating . The coating shall be done on Reclaimed Concrete Surface thoroughly cleaned of dust & debris and scarified after removal of damaged Acid Resistant Tiles and instruction of the Engineer in charge. (Price inclusive of all taxes, supply of Materials, loading unloading transportation, labour and all bye works complete in all respect.)	300	sqm				
		Total :		Rs			

Over all rebate, if any -----(in words and figures)

Net Total _____

Note : 1) All the rates must be written in figures and words clearly without which tenders are likely to be rejected.

2) All the pages of tender document including price part must be duly signed by the tenderer along with their seal, without which tenders may likely to be rejected.

* * * * *