

Schedule of quantities for : Drilling bore holes and grouting and Permeability tests in extended base of Tailings dam at Turamdih

Ref NIT No. TMD / 579 dt 12.04.2014

Item No.	Description in short	Qty	Unit	Rate	Rate	Amounts
				in figure	in words	
1	Complete mobilization of men and machinaries such as grouting Mixer plant, Grout pump, Permeability test arrangement and accessories and all other tools, tackles required for completing the work successfully		L.S.			
2	Drilling of 40mm dia bore hole up to an avg. depth of 6 mtrs or as directed by EIC including all necessary tools and tackles ,machinaries, men and materials required for the work	3720	RM			
3	Drilling of 75mm dia bore hole up to an avg. depth of 6 mtrs or as directed by EIC including all necessary tools and tackles ,machinaries, men and materials required for the work	744	RM			
4	Execution of work of grouting as per IS-6066/1994 below the dam all along the alignment to improve the impermeability to preclude the possibility of under seepage as well as filling the cracks and fissures in the rock and submission of all report/document	89000	kg			

Item No.	Description in short	Qty	Unit	Rate	Rate	Amounts
				in figure	in words	
5	Performing field permeability test at various stages of grouting with suitable pressure as applicable and submission of all relevant report/ documents for all stage of test	124	Each			
				TOTAL COST	Rs	
Over all rebate, if any -----(in words and figures)						
				Net Total	Rs	
<p>Note : 1) All the rates must be written in figures and words clearly without which tenders are likely to be rejected.</p> <p>2) All the pages of tender document including price part must be duly signed by the tenderer along with their seal, without which tenders may likely to be rejected.</p> <p style="text-align: center;">* * * * *</p>						